

EXHIBIT "B"

2024 OVERLAY PROJECT - SPECIAL PROVISIONS

#1. Full width mill road surface to a depth of 2". Asphalt shall be applied with a 1" leveling and a 1.5" top lift to the 2.5" overlays for Project #1

#2 Installation of Fabric for Proj. #2 must be performed by trained and approved installers. Spray milled surface with .15 gal/ yd² of AC 10 PG 58-28 asphalt cement binder and install Mirafi MPM30 immediately after binder is applied with distributor truck. The asphalt binder shall be applied at a temperature between 350 and 400 degrees F. All wrinkles or " dryfolds" in the MPM30 fabric over 1 inch must be cut and laid down flat. Paver shall follow behind applying asphalt with a single 2.5" lift for Project #2.

#3. Hand patch with HMA (hot mix asphalt) any irregularities left from milling process.

#4. The hot mix asphalt shall be no less than 260 degrees F behind the paver as it is applied.

#5. Proj. #1 Milled asphalt will be hauled to location near job site (Sheep Gulch).
Proj. #2 Milled asphalt can be hauled to Eagle County Landfill if Contractor has no use for them

#6. Contractor shall be responsible for manhole and valve box counts.

#7. Materials testing and sampling shall be performed at 500 ton intervals or a minimum of one per day.

#8. Contractor shall be responsible for notification of project dates to affected residents and motorists including detours and delays. Contractor shall notify Road and Bridge Director of any necessary detours and provide an MHT.

#9. Each project will be looked at individually to determine bid awards.

#10. Contractor shall be responsible for measuring and calculating all quantities for bid.

#11. Material quantities may be adjusted depending on bid results.