

**EAGLE COUNTY LANDFILL
LEACHATE HOLDING POND CONSTRUCTION PROJECT
EAGLE COUNTY LANDFILL
815 UTE CREEK RD.
WOLCOTT, CO 81655**

Addendum No. 2

1. **Q:** Can fence posts be reused (reference to Bid Item No. 21)?
A: Existing fence posts will have concrete on them; therefore they will not be reusable. Contractor should plan on replacing fence posts for the indicated linear feet of fencing in Bid Item No. 21. Existing fence posts will be disposed of by the Contractor in the active area of the landfill.

2. A revision to the fence detail should be noted. Attached to this Addendum No. 2 is a revised detail and revised specification Section 32 31 13, Chain Link Fences and Gates. The revised new fence components to be supplied for this project are:
 - Chain Link Fabric: 2-inch diamond-mesh interwoven wire, 9-gauge thick, top selvage twisted tight, bottom selvage knuckle end closed
 - Line Posts: 2-3/8 inch diameter
 - Corner and Terminal Posts: 2-7/8 inch diameter
 - Top and Brace Rails: 1-5/8 inch diameter
 - Tie Wire: 9 gauge aluminum alloy

3. **Q:** What is the roundtrip distance for the LHP work area to the working face of the landfill in which the Contractor shall dispose of materials?
A: The roundtrip distance from the LHP work area to the working face of the landfill is 1.6 miles.

4. **Q:** Will there be any shale excavation?
A: There is a potential for shale excavation. A revised Bid Form is attached to this Addendum No. 2 with new Bid Item 27.0: Shale Excavation.

5. **Q:** Line item 3.2 lists fill at 5178 cy. Is this the correct amount of fill?
A: The fill amount listed in Bid Item 3.2 is correct. This estimated fill quantity was calculated by comparing existing ground elevations from current topo information with the design final subgrade elevations.