

EXHIBIT "B"
2019 OVERLAY PROJECT - SPECIAL PROVISIONS

- #1.** Installation of fabric must be performed by trained and approved installers.
- #2.** Spray top of existing asphalt surface with .15 gal per square yard of AC 10 PG 58-28 asphalt cement binder and Install Mirafi MPM30 on existing asphalt surface immediately after binder is applied with a distributor truck. The asphalt binder shall be applied at a temperature of between 350 and 400 degrees F. Paver shall follow behind the fabric installation with a 2.25" overlay.
- #3.** All wrinkles or "dry folds" in the MPM30 fabric over 1" must be cut and laid down flat.
- #4.** All roads in EXHIBIT "A" shall receive Mirafi MPM30 material.
- #5.** Contractor shall be responsible for measuring and calculating all quantities for bid.
- #6.** Material quantities may be adjusted depending on bid results.
- #7.** The hot mix asphalt shall be no less than 260 degrees F behind the paver as it is applied.
- #8.** Materials testing and sampling shall be performed at 400 ton intervals.
- #9.** Contractor shall be responsible for notification of project dates to affected residents and motorists including detours and delays. Contractor shall notify Road and Bridge Director of any necessary detours and provide an MHT.
- #10.** Asphalt shall be applied with a single 2.25" lift.
- #11. ROAD LIST:**
Frying Pan River Road from Basalt City limits to the 4 Mile Marker plus or minus depending on bid results.